



OHIO DEPARTMENT OF TRANSPORTATION

DISTRICT 02

317 E. POE RD. • BOWLING GREEN, OH 43402 • 419-353-8131

Environmental Document

for

HEN SR 110 1.150 Resurf PID 94321

Environmental Document Level: C1

Approved: 11/30/2018

Prepared By: District 2

Phoenix Neal

Phone: 419-373-4329

E-mail: Phoenix.Neal@dot.ohio.gov

The environmental review, consultation, and other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by ODOT pursuant to 23 U.S.C. 327 and a Memorandum of Understanding dated December 11, 2015, and executed by FHWA and ODOT.

Table of Contents

C1.....	3
Environmental Commitments.....	4
Preparers and Approvals.....	5
Appendix.....	6



C1

PID: 94321
Project Sponsor: DISTRICT 2 PRODUCTION
ODOT District: 2
Funding Source: Federal
Private Funding: No

Project Description:

The Ohio Department of Transportation (ODOT) is proposing to resurface State Route 110 in Henry County from State Route 109 to Perry Street in Napoleon. These repairs will not require right of way and will not impact utilities. There will be no impacts to any waterways so no permits from the US Army Corps of Engineers is required. This project does not pass through any floodplains so floodplain coordination is not required. There will be no impacts to any ecologically significant resources. Since there is no work outside of the right of way and there are no historic districts near this project, there is minimal potential to cause effects on historical resources. Construction is expected to begin in summer 2021 and last approximately 45 days total. During construction, a minimum of one lane will be maintained at all times.

This document was written and approved based on the work limits stated in Ellis.

STIP Reference # SLI 32
Cultural Resources Coordination: Minimal Potential to Cause Effect
Appendix A
Cultural Resources Coordination Date: 11/08/2017

Since no Tribe was interested in this project based on their customized preferences, no further Tribal consultation was conducted.

Supporting documentation has been uploaded to Project File: Yes

Select the appropriate project type (more than one can be selected):

(23) Projects that receive less than \$5,179,656.40 of Federal funds or with a total estimated cost of not more than \$31,077,938.40 and with Federal funds that comprise less than 15 percent of the total estimated project cost *(each amount adjusted annually by the Secretary to reflect any increases in the Consumer Price Index prepared by the Department of Labor, see www.fhwa.dot.gov or www.fta.dot.gov).*

Environmental Commitments: Yes



Environmental Commitments

C1

1) The Project Designer shall incorporate the following note into the plans: This project is located in or near public drinking water sources. In order to minimize the potential for a release in this sensitive area do not perform equipment fueling on SR-110 from SLM 1.15 to 1.24. If refueling of immobile equipment is necessary within these limits, provide secondary containment with enough capacity to completely contain and collect all potential liquid wastes in the event of a spill. Do not perform maintenance activities associated with any viscous material that has potential to contaminate the groundwater. All equipment or liquid containers shall be regularly checked for leaks prior to entering the restricted areas. The contractor shall develop a Spill Prevention Control and Countermeasure Plan (SPCC) if refueling or maintenance will be performed within the project limits in the table below. If any refueling or maintenance will be performed outside of the project limits, the area shall be assessed for potential groundwater contamination and be indicated on the Spill Prevention Control and Countermeasures Plan. The Contractor shall immediately take steps to mitigate any event, such as a spill of fuels, oils, or chemicals. Any such spill or event shall be reported immediately to the emergency contact listed below for each drinking water source. If the spill is a reportable amount, the Contractor should contact Henry County Emergency Management (419-592-4876) and Ohio EPA Environmental Response and Revitalization (419-373-3031 or 800-282-9378) for cleanup of the spill.



Environmental Document Level: C1
PID 94321 HEN SR 110 1.150 Resurf
Approved: 11/30/2018

Preparers and Approvals

Form Preparer

District 2
Contact: Phoenix Neal
419-373-4329
Phoenix.Neal@dot.ohio.gov

Approvals & Electronic Signatures

Approved & Electronically Signed By:	Approval Date:
Phoenix Neal (ENV SPEC 2)	11/30/2018



Appendix

General

Aerial Map.pdf

County Map.pdf

USGS Quadrangle Topographical Map.pdf

ESA

Regulated Materials Map.pdf

Regulated Materials Review Form.pdf

Ecological

Ecological Review Form - Ecologically Exempt Project.pdf

Permits

FEMA FIRM.pdf